



REMARKS:

- Arrows toward unit show RETURN air option.
- Arrows away from unit show SUPPLY option.
- Water Inlet / Outlet = 1/2" FPT off Chassis.
- Condensate Drain = 3/4" ID Hose.
- Disposable Filter Included (16" H X 24" W X 1" T).
- 24" long Supply, Return and Condensate Hose Included. (Includes Cabinet, Chassis, Panel and Boot)

- A - 18" x 9" KnockOuts for Supply Ducting
- B - 16" x 8" KnockOut for Supply Ducting
- C - 16" x 4" Optional KnockOut Extension
- D - KnockOut for Flex. Hose Connection of Risers to Chassis or for Return Air
- E - Electrical Box / KnockOuts for Electrical Connections
Box Size (4.50" H X 3" W X 2.38" D)
- F - Optional Cabinet Base Extensions (Various Heights Available)

THE INFORMATION CONTAINED IN THIS DRAWING IS THE SOLE PROPERTY OF CGC Group. ANY REPRODUCTION IN PART OR AS A WHOLE WITHOUT THE WRITTEN PERMISSION OF CGC Group IS PROHIBITED.



HKV 016-030		
PRODUCT REVISION(S):	L	
DATE(MM/DD/YYYY):	12/03/2025	REV: A
DESCRIPTION:	Standard Submittal Drawing for HomeKeeper Vertical Stacked Hybrid R454B w/ Universal Cabinet	