



i) RETURN AIR OPENING
 ii) Base Opening to provide sufficient spacing for contractor to connect Building Water In/Out Connection on units

REMARKS:

- ① WATER IN 1/2" FPT, 2 FT HOSE INCLUDED
- ② WATER OUT 1/2" FPT, 2 FT HOSE INCLUDED
- ③ POWER CORD INCLUDED
- ④ CONDENSATE DRAIN 3/4" ID HOSE INCLUDED
- ⑤ 1" THICK DISPOSABLE FILTER INCLUDED (37"X11")
- ⑥ FAN HOUSING
- ⑦ HOT WATER AND DX COIL
- ⑧ STANDARD BASE (5")
- ⑨ THERMOSTAT DRAWER (ONLY WITH THERMOSTAT MOUNTED UNITS)

<p>PROPRIETARY AND CONFIDENTIAL</p> <p>UNLESS OTHERWISE SPECIFIED: DIMENSIONS ARE IN INCHES</p> <p>TOLERANCES UNLESS OTHERWISE NOTED ARE: FRACTIONAL ± 1/16" ANGULAR ± 0.5° .X ± .1" .XX ± .06" .XXX ± .032" .XXXX ± .0050"</p>	NAME: A.D DATE (MM/DD/YYYY): 05/15/2020	DRAWING: BULLDOG SPACEKEEPER CONSOLE SIZE 018 (SKC 018)
	CHECKED: F.S DATE: 05/15/2020	
FINISH:		SCALE: NTS WEIGHT: SHEET 1 OF 1